



Pathway Keyplan 1:1250

- New pathways (bitumen with PCC pin kerb)
- Pathway resurfacing (bitumen overlay, reset existing kerbs)
- Pathway patch repairs (bitumen overlay)
- Reclaimed blue terracotta edging (to new pathway to north of pool only)
- Stone retaining wall structure to north of pool
- New cobble setts (2 x strips)

Brinton Park Pathway Improvements

New pathways (bitumen with PCC pin kerb, unless stated as otherwise below)

- a New section of pathway to north of reinstated pool (with reclaimed terracotta edging)
- b New section of pathway leading to car park
- c New ramped pathway leading to Sons of Rest Pavilion terrace

Pathway Resurfacing (bitumen overlay, reset existing kerb)

- R Resurface small section of pathway linking Senses Garden to pool area
- l Resurface pathways to leading up to Sons of Rest Pavilion
- m Resurface small section of pathway to south side of reinstated pool
- n Resurface full length of pathway to east of reinstated pool
- o Resurface small section of pathway (approx. 10m long)
- p Resurfacing to Stourport Road / Park Lane entrance

Pathway Patch Repairs (bitumen overlay)

- q Patch repairs to small section of pathway

The following risks are identified as unusual or unfamiliar to a competent contractor

CONSTRUCTION RISKS
There are no significant or unfamiliar risks

DEMOLITION RISKS (FUTURE)
There are no significant or unfamiliar risks

It is assumed that all work will be carried out by a competent contractor working, where appropriate, to an approved method statement

Notes:

